ROOM SCHEDULE

NUMBER	NAME	BASE FINISH	FLOOR FINISH	WALL FINISH	CEILING FINISH	AREA
#1	STAIR					168 SF
#2	STAIR					168 SF
100	ATRIUM					1800 SF
101	RECEPTION & WAITING					313 SF
102	OPEN OFFICE					1977 SF
103	CONFERENCE ROOM					204 SF
104	WORK ROOM					437 SF
105	WOMENS	COVED CT.	GYP. BD.	CT	CT	163 SF
106	MENS	COVED CT.	GYP. BD.	CT	CT	163 SF
107	MECH / ELEC RM					133 SF
108	BREAK ROOM					393 SF
109	OFFICE					101 SF
110	OFFICE					138 SF
111	OPEN OFFICE					2313 SF
200	ATRIUM					1003 SF
201	OPEN OFFICE					3000 SF
202	TELECOMM					133 SF
203	OPEN OFFICE					3000 SF
204	WOMENS	COVED CT.	GYP. BD.	CT	CT	163 SF
205	MENS	COVED CT.	GYP. BD.	CT	CT	163 SF
300	ATRIUM					1003 SF
301	OPEN OFFICE					2027 SF
302	OFFICE	WOOD	CARPET 1	VWC 1	ACT 1	229 SF
303	OFFICE	WOOD	CARPET 1	VWC 1	ACT 1	165 SF
304	OFFICE	WOOD	CARPET 1	VWC 1	ACT 1	165 SF
305	OFFICE	WOOD	CARPET 1	VWC 1	ACT 1	229 SF
306	OFFICE	WOOD	CARPET 1	VWC 1	ACT 1	125 SF
307	MECH / ELEC RM					133 SF
308	OPEN OFFICE					2027 SF
309	STORAGE					125 SF
310	OFFICE	WOOD	CARPET 1	VWC 1	ACT 1	229 SF
311	OFFICE	WOOD	CARPET 1	VWC 1	ACT 1	165 SF
312	OFFICE	WOOD	CARPET 1	VWC 1	ACT 1	165 SF
313	OFFICE	WOOD	CARPET 1	VWC 1	ACT 1	229 SF
314	WOMENS	COVED CT.	GYP. BD.	CT	CT	163 SF
315	MENS	COVED CT.	GYP. BD.	CT	CT	163 SF

DOOR SCHEDULE

MARK	WIDTH	HEIGHT	FRAME MATERIAL	FRAME TYPE	FIRE RATING
1A	3' - 0"	7' - 0"			
1B	3' - 0"	7' - 0"			
2A	3' - 0"	7' - 0"			
2B	3' - 0"	7' - 0"			
100A	3' - 1 1/2"	7' - 10 3/4"			
100B	3' - 1 1/2"	7' - 10 3/4"			
100C	3' - 0"	7' - 0"			
100D	3' - 0"	7' - 0"			
101	6' - 0"	7' - 0"			
102	6' - 0"	7' - 0"			
103	3' - 0"	7' - 0"			
104A	3' - 0"	7' - 0"			
104B	3' - 0"	7' - 0"			
105	3' - 0"	7' - 0"			
106	3' - 0"	7' - 0"			
107	3' - 0"	7' - 0"			
108	3' - 0"	7' - 0"			
109	3' - 0"	7' - 0"			
110	3' - 0"	7' - 0"			
111A	6' - 0"	7' - 0"			
111B	3' - 0"	7' - 0"			
201A	6' - 0"	7' - 0"			
201B	3' - 0"	7' - 0"			
201C	3' - 0"	7' - 0"			
202	3' - 0"	7' - 0"			
203A	6' - 0"	7' - 0"			
203B	3' - 0"	7' - 0"			
203C	3' - 0"	7' - 0"			
204	3' - 0"	7' - 0"			
205	3' - 0"	7' - 0"			
301A	6' - 0"	7' - 0"			
301B	3' - 0"	7' - 0"			
301C	3' - 0"	7' - 0"			
302	3' - 0"	7' - 0"			
303	3' - 0"	7' - 0"			
304	3' - 0"	7' - 0"			
305	3' - 0"	7' - 0"			
306	3' - 0"	7' - 0"			
307	3' - 0"	7' - 0"			
308A	6' - 0"	7' - 0"			
308B	3' - 0"	7' - 0"			
308C	3' - 0"	7' - 0"			
309	3' - 0"	7' - 0"			
310	3' - 0"	7' - 0"			
311	3' - 0"	7' - 0"			
312	3' - 0"	7' - 0"			
313	3' - 0"	7' - 0"			
314	3' - 0"	7' - 0"			
315	3' - 0"	7' - 0"			

SIERRA COLLEGE

www.autodesk.com/revit

Consultant
Address
Address
Phone
Fax
e-mail

Consultant
Address
Address
Phone
Fax
e-mail

Consultant
Address
Address
Phone
Fax
e-mail

Consultant
Address
Address
Phone
Fax
e-mail

Consultant
Address
Address
Phone
Fax
e-mail

No.	Description	Date

OFFICE BUILDING

404 Error Lane

SCHEDULES

Project number	16384-2018
Date	11-26-18
Drawn by	EASTMAN, DANIEL
Checked by	Checker

A-800

Scale

4/2/2019 1:54:25 PM